

TRM + VLR

Used in parallel masonry. The bent end is bricked in first. The insulation is pressed in the tie and fastened with a counter plate (VLR). The end of the tie is bent into the brick seam. Minimum length: insulation thickness + air gap + 180mm. Rustproof parts. Available in 4mm and 5mm. Consumption 4-5 pcs/m².

