

SHR + VLR + TS

Wall tie preinstalled in concrete. SHR is embedded into concrete through the insulation. After the concrete is dry, install a counter plate (VLR) to fasten the insulation. The brick tie is installed at the worksite. SHR length: insulation + 110mm. Rustproof parts. Available in 4mm and 5mm. Consumption 4-5 pcs/m².

CE approved

