

SH + VLR

Wall tie preinstalled in concrete. SH is embedded separately through the concrete. After the concrete is dry, install a counter plate (VLR) to fasten the insulation. The end of SH is bent into the brick seam at the worksite.

Length: installation + air gap + 210mm. Rustproof parts.

Available in 4mm and 5 mm. Consumption 4-5 pcs/m².

CE approved

